

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	52 U-1785-01	2003	68	143

DATE	BY	REFERENCES NOTED	REFERENCES CHECKED
9-01	M Adams		
11-01	R Skagman		

SYMBOL KEY

-  REMOVE SIGN
-  REMOVE POST
-  REMOVE FOOTING
-  REMOVE SIGN & POST
-  REMOVE POST & FOOTING
-  REMOVE SIGN, POST, & FOOTING
-  MOUNT ON WOOD POST IN CONCRETE FOOTING
-  MOUNT ON WOOD POST IN SOIL
-  MOUNT ON STEEL BEAM BREAKAWAY POST
-  MOUNT ON STEEL U-POST
-  MOUNT ON PERFORATED SQUARE STEEL TUBE
-  MOUNT ON EXISTING POST
-  MOUNT ON VERTICAL SUPPORT
-  SHOULDER MOUNTED INSTALLATION
-  OFFSET MOUNTED INSTALLATION
-  EXISTING SIGN
-  EXISTING SIGN TO BE OVERLAID
-  SIGN IS NOT PART OF PROJECT
-  TYPE 'A' DELINEATOR (RIGID)
-  TYPE 'B' DELINEATOR (RIGID)
-  TYPE 'A' DELINEATOR (FLEXIBLE)
-  TYPE 'B' DELINEATOR (FLEXIBLE)
-  TYPE 2 OBJECT MARKER
-  TYPE 3 OBJECT MARKER

GENERAL NOTES

In order to expedite the completion of the project for traffic service, the Signing and Delineator work shall be sequenced with any other contract work such that the phases of construction may proceed and be completed at the same time.

New signs erected on the project which are in conflict with existing signing are to be completely covered until the existing signs are removed or the new signing is applicable. The existing signs that are being replaced, removed, or do not follow the current MUTCD signing standards are to be removed when the project is completed or as determined by the Engineer.

The contractor shall exercise caution at all times when installing sign supports in and around areas where utilities exist, either underground or overhead, and will be held responsible for any damage incurred to the system. The installation of sign supports shall include the excavation, drilling, or driving the support footing and the erection of the sign support. The contractor shall exercise caution when working around any existing signs that are to remain and will be held responsible for any damage to the signs, supports, or footings. The contractor shall exercise care when working around shrubbery while removing or installing signs or sign supports.

An existing sign post installation shall be plumb and the compaction of the backfill soil shall comply with the specifications after the removal and resetting of a sign, the removal and replacement of a sign, or the installation of a new sign.

The Contractor shall provide mounting bolts that are of a length that does not extend more than a nominal 1 inch beyond the sign post. The Contractor shall not make any field modifications to the mounting bolt prior to or after the sign is installed.

The materials and fabrication for Signing and Delineation work shall conform to the Standard Specifications for State Road and Bridge Construction (1990 Edition) and Special Provisions.

INDEX OF SHEETS

- 68 SIGNING SYMBOL KEY, GENERAL NOTES, AND INDEX
- 69 DETAILS FOR MOUNTING HEIGHTS, LATERAL OFFSETS, AND LONGITUDINAL ADJUSTMENTS
- 70 DETAILS FOR PERFORATED SQUARE STEEL TUBE POSTS (PSST)
- 71 QUANTITIES SHEET (SIGNS, POSTS, & FOOTINGS TO BE INSTALLED ON PROJECT)
- 72 SUMMARY OF QUANTITIES FOR INSTALLATIONS AND REMOVALS
- 73 SUMMARY OF QUANTITIES FOR REMOVAL AND RESETTING OF SIGNS
- 74 RECAPITULATION OF SIGNING & DELINEATION BED ITEMS
- 75 SIGN BLANK DETAILS FOR FLAT SHEET SIGNS
- 76 SIGN BLANK DETAILS FOR FLAT SHEET SIGNS
- 77 DETAILED SPECIFICATIONS FOR REINFORCED SIGN PANELS AND FLAT SHEET SIGNS

Plotted : 4/16/2004
 Drawn By : rsteamman
 File : P:\0154\0154\te402si.dgn

3				
2				
1				
NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION
 SIGNING SYMBOL KEY,
 GENERAL NOTES, AND INDEX

TE402si 07-01-03

DESIGNED	DDG	DETAILED	WSB	QUANTITIES	TRACED
DESIGN CK.	SAB	DETAIL CK.	DDG	QUAN. CK.	TRACE CK.